



PlatinumStripe® 1800 Series PE-RT Pipe Specifications

HDPE Pipe and Fittings for High Temperature Applications (PE-RT)

Questions? Get Technical Advice 800-345-ISCO (4726)

PART 1 – GENERAL

1.01 SCOPE OF WORK

- A. This specification covers the material (pipe and fittings), joining methods and general installation practice for high density polyethylene pipe (HDPE) piping systems for high temperature applications.

1.02 SUBMITTALS

- A. Submit product data to the Engineer for review in accordance with the Section XXXXX for all pipe, fittings, and appurtenances.
- B. Contractor shall also submit the following to the Engineer for approval:
1. Certified dimensional as-built drawings/profile of all installed pipe, specials and fittings.
 2. Details of fittings and specials such as elbows, tees, outlets, connections, test bulkheads, nozzles or other special items where shown on the Construction Drawings. All connections to jointed gasketed pipe materials, valves or fire hydrants must be restrained and supported independently to withstand the pressure transients, soil settlement, and external loading conditions.
 3. The Supplier of the material shall submit, through the Contractor, a Certificate of Compliance that the PE-RT pipe and fittings furnished for this project meet or exceed the standards set forth in this specification. The Contractor shall submit these certificates to the Engineer prior to installation of the pipe materials.
 4. Provide a certification that personnel responsible for fusing the pipe have been trained and qualified per ASTM F3190
- C. For items that do not meet all of the requirements of this specification, the bid/submittal shall include a written description of the deviations, along with data that show the magnitude and the justification for the deviation from the specification. The decision to accept material deviating from this specification shall be the responsibility of the specifying engineer and must be approved in writing.

1.03 REFERENCE DOCUMENTS AND STANDARDS

The standards and documents listed below may apply to the materials and practices in this specification. In the event of a conflict, the requirements of this specification prevail. Unless otherwise specified, references to documents shall mean the latest published edition of the referenced document in effect at the project bid date.

PLASTICS PIPE INSTITUTE, PPI

- PPI Handbook of Polyethylene Pipe – 2009 (2nd Edition)
- PPI Municipal Advisory Board (MAB) MAB-01 Generic Electrofusion Procedure for Field Joining of 12 Inch and Smaller Polyethylene (PE) Pipe
- PPI Material Handling Guide for HDPE Pipe and Fittings

Questions? Get Technical Advice 800-345-ISCO (4726)

- PPI TR-33 Generic Butt Fusion Joining Procedure for Field Joining of Polyethylene Pipe
- PPI TR-34 Disinfection of Newly Constructed Polyethylene Water Mains
- PPI TN-38 Polyethylene Flanged Joints
- PPI TR-41 Generic Saddle Fusion Joining Procedure for Polyethylene Gas Piping
- PPI TR-46 Guidelines for Use of Mini-Horizontal Directional Drilling for Placement of High Density Polyethylene Pipe

ASTM

- ASTM D2321 Standard Practice for Underground Installation of Thermoplastic Pipe for Sewers and Other Gravity-Flow Applications
- ASTM D2683 Standard Specification for Socket-Type Polyethylene Fittings for Outside Diameter-Controlled Polyethylene Pipe and Tubing
- ASTM D2774 Standard Practice for Underground Installation of Thermoplastic Pressure Piping
- ASTM F2880 Standard Specification for Lap-Joint Type Flange Adapters for Polyethylene Pressure Pipe in Nominal Pipe Sizes 3/4 in. to 65 in.
- ASTM D3035 Standard Specification for Polyethylene (PE) Plastic Pipe (DR-PR) Based on Controlled Outside Diameter
- ASTM D3261 Standard Specification for Butt Heat Fusion Polyethylene (PE) Plastic Fittings for Polyethylene (PE) Plastic Pipe and Tubing
- ASTM D3350 Standard Specification for Polyethylene Plastics Pipe and Fittings Materials
- ASTM F585 Standard Guide for Insertion of Flexible Polyethylene Pipe Into Existing Sewers
- ASTM F714 Standard Specification for Polyethylene (PE) Plastic Pipe (DR-PR) Based on Outside Diameter
- ASTM F1055 Standard Specification for Electrofusion Type Polyethylene Fittings for Outside Diameter Controlled Polyethylene and Crosslinked Polyethylene (PEX) Pipe and Tubing
- ASTM F1417 Standard Practice for Installation Acceptance of Plastic Non-pressure Sewer Lines Using Low-Pressure Air
- ASTM F1962 Standard Guide for Use of Maxi-Horizontal Directional Drilling for Placement of Polyethylene Pipe or Conduit under Obstacles, Including River Crossings
- ASTM F2164 Standard Practice for Field Leak Testing of Polyethylene (PE) and Crosslinked Polyethylene (PEX) Pressure Piping Systems Using Hydrostatic Pressure
- ASTM F2206 Standard Specification for Fabricated Fittings of Butt-Fused Polyethylene (PE)
- ASTM F2620 Standard Practice for Heat Fusion Joining of Polyethylene Pipe and Fittings
- ASTM F3124 Standard Practice for Data Recording the Procedure Used to Produce Heat Butt Fusion Joints in Plastic Piping Systems or Fittings

Questions? Get Technical Advice 800-345-ISCO (4726)

- ASTM F3183 Standard Practice for Guided Side Bend Evaluation of Polyethylene Pipe Butt Fusion Joint
- ASTM F3190 Standard Practice for Heat Fusion Equipment (HFE) Operator Qualification on Polyethylene (PE) and Polyamide (PA) Pipe and Fittings
- ASTM F1804 Standard Practice for Determining Allowable Tensile Load for Polyethylene (PE) Gas Pipe During Pull-In Installation
- ASTM B843 Standard Specification for Magnesium Alloy Anodes for Cathodic Protection

PART 2 – PRODUCTS**2.01 HIGH DENSITY POLYETHYLENE MATERIALS****A. RESIN AND MATERIAL REQUIREMENTS**

1. PE-RT material used for the manufacture of polyethylene pipe, tube and fittings shall be PE 4710 high density polyethylene meeting ASTM D3350 cell classification of 445574C and shall be listed in the name of the pipe and fitting manufacturer in PPI (Plastics Pipe Institute) TR-4 with a standard grade HDB rating of 1600 psi at 73°F and 800 psi at 180°F per ASTM D2837. The material shall contain a stabilizer system for high oxidative environments with a CC3 rating per ASTM D3350.

B. PE-RT PIPE

1. PE-RT pipe shall be manufactured in accordance with ASTM F2619, API 15LE and ASTM F714. The pipe shall be protected against UV degradation with 2-3% carbon black.

Approved Pipe: PlatinumStripe® 1800 Series PE-RT Pipe

2. IPS pipes shall have four, equally spaced, platinum color stripes co-extruded into the pipe outside surface. Stripes printed or painted on the pipe outside surface shall not be acceptable.
3. Pipe shall be marked in accordance with ASTM F2619, API 15LE and ASTM F714.

C. PE-RT FITTINGS

1. **Butt Fusion Fittings** - Fittings shall be made of PE-RT HDPE material with a minimum material designation code of PE4710 and with a minimum Cell Classification as noted in 2.01.A. Fittings shall have a minimum pressure rating equal to or greater than the pipe to which they are joined unless otherwise specified on the plans or accepted by owner/engineer.
 - a. Molded fittings shall comply with the requirements of ASTM D3261.
 - b. All fabricated elbows, tees, reducing tees and end caps shall be produced and meet the requirements of ASTM F2206, as manufactured by ISCO Industries, Inc or other approved manufacturer holding an ISO 9001 quality system certificate. Each fitting will be marked per ASTM F2206 section 10 including the nominal size and fitting EDR, which will meet or

Questions? Get Technical Advice 800-345-ISCO (4726)

exceed the pipe DR identified for the project. Fabricated fittings shall be manufactured using a data recording device to record fusion pressure and temperature, and shall be stamped with unique joint number that corresponds to the joint report. A graphic representation of the temperature and pressure data for all fusion joints made producing fittings shall be maintained for a minimum of 5 years as part of the quality control and will be available upon request of owner. Test results to validate ASTM F2206 section 7.3 and 9 shall be provided to owner or owner's representative upon request.

2. **Bolted Connections** – Flanged and Mechanical Joint Adapters can be made to ASTM D3261. Flange adapters, if machined, may also meet the requirements of ASTM F2880. Flanges and MJ Adapters shall be fused onto the pipe and have a minimum pressure rating equal to or greater than the pipe unless otherwise specified on the plans.
 - a. Metallic back-up rings (Van-Stone style lap joint flanges), shall have a radius on the inside diameter of the bore so as to be compatible with PE-RT Flanges. Back up rings shall have bolt pattern that will mate with AWWA C207 Class D (or B or E), ASME/ANSI B 16.5 Class 150, ASME/ANSI B 16.1 Class 125, or ASME/ANSI B16.47 Series A..
 - b. Flange assemblies shall be assembled and torqued according to PPI TN-38, "Bolt Torque for Polyethylene Flanged Joints."
 - c. Where shown on the drawings, 4" and larger transitions to mechanical joint fittings and valves shall be accomplished using a MJ Adapter with kit. The D.I./HDPE mechanical joint adaptor shall consist of:
 - i. A molded or fabricated HDPE mechanical joint transition fitting.
 - ii. A rubber gasket.
 - iii. A mechanical joint backup drive ring.
 - iv. Corten mechanical joint tee bolts.
3. **Mechanical Fittings:** The use of mechanical coupling and saddles shall be approved by the owner or engineer prior to installation. Mechanical Fittings shall be designed for use and compatible with PE-RT pipe. Mechanical fittings shall have a pressure rating equal to or greater than the pipe.
 - a. Couplings without self-restraining capabilities (integrated serrated teeth or grippers) shall include a plan for external restraint or isolation from pipeline generated forces.
 - b. Mechanical Saddles shall have wide straps for distribution of clamping loads. No U- bolts shall be allowed.
 - c. When required by mechanical coupling manufacturer, pipe stiffeners shall be employed to support the interior wall of the PE-RT. The stiffeners shall support the pipe's end and control the "necking down" reaction to the pressure applied during normal installation. The pipe stiffeners shall be formed of 304 or 316 stainless steel, with a wedged style design to fit the PE-RT manufacturers published average inside diameter of the specific size and DR of the PE-RT.

Questions? Get Technical Advice 800-345-ISCO (4726)**D. FUSION UNIT REQUIREMENTS**

1. All Fusion Equipment, whether new or used, rented or owned, shall comply with the requirements of ISO 12176-1 "Equipment for Fusion Jointing Polyethylene Systems".
2. Butt fusion equipment must be in satisfactory working order and the hydraulic system must be leak free. Heater plates shall be free from scrapes, gouges, and have a consistent clean coated surface. The pressure gauge and thermometer should be properly calibrated. When requested by the owner, records showing a maintenance service/inspection within 3 months prior to use for this project shall be provided.
3. Rental Butt Fusion Equipment must be maintained by a McElroy Authorized Service and Repair Center with at least one McElroy Certified Master Mechanic on staff. When requested by owner or his authority, an inspection report detailing the components inspected within 3 months prior to arrival at jobsite will be provided.
4. For 16" and larger pipe sizes, the butt fusion machine shall be capable of autonomously calculating the drag pressure and perform the shift sequence autonomously.

E. APPROVED SUPPLIERS

1. All Pipe, Fittings, and Fusion Equipment shall be provided by one supplier. Approved suppliers are ISCO Industries, Inc. or approved equal.

2.02 PIPELINE LOCATING MATERIALS

- A. **Detectable Marker Tape** - Plastic marker tape shall be 5 mil minimum thickness with a solid aluminum core of .35mil minimum thickness and a minimum width of 2". The background of the tape shall be colored based on pipe service with black lettering continuously printed. Marker tape shall have a minimum 35 lbs./inch tensile strength. The installation of the tape shall be at 18 inches below finish grade.
- B. **Tracer Wire** - All PE-RT pipe 4" and greater shall be installed with an extra high-strength, copper clad steel tracer wire including 45 mil HDPE jacket that has a minimum average break load of at least 1150 lbs. The jacket shall be colored based on pipe service, with blue for potable water or green for sewer. Tracer wire gauge shall be 12 AWG, 10 AWG, or 8 AWG depending upon application and installation procedure. This wire shall to be continuous and brought up in the valve boxes at the ends of each line segment with splices made only by methods per the equipment manufacturer's recommendation. All miscellaneous splicing components shall be furnished and installed by the Contractor.

PART 3 – EXECUTION**3.01 GENERAL**

- A. All PE-RT pipe and fittings shall be cut, joined, and installed in accordance with the manufacturer's recommendations. Joining, laying, and pulling of polyethylene pipe shall be accomplished by personnel experienced in working with polyethylene pipe systems.

Questions? Get Technical Advice 800-345-ISCO (4726)**3.02 TRANSPORTATION, UNLOADING, AND STORAGE**

- A. The manufacturer shall package product in a manner designed to deliver the pipe and fittings to the project neatly, intact and without physical damage. During transportation each pipe shall rest on suitable pads, strips skids, or blocks securely wedged or tied in place.
- B. During loading, transportation, and unloading, every precaution should be taken to prevent damage to the pipe. The handling of the pipeline shall be in such a manner that the pipe is not damaged by dragging it over sharp and cutting objects. Cuts or gouges that reduce the wall thickness by more than 10% are not acceptable and must be cut out and discarded.
- C. Handle the pipe in accordance with the PPI Handbook of Polyethylene Pipe (2nd Edition), Chapter 2. All pipe and accessories shall be loaded and unloaded by lifting with hoists or by skidding in order to avoid shock or damage. Under no circumstances shall materials be dropped. Pipe handled on skidways shall not be rolled or skidded against pipe on the ground. Slings, hooks or pipe tongs shall be padded and used in such a manner as to prevent damage to the exterior surface or interior of the pipe. All pipe and fittings shall be subjected to visual inspection at time of delivery and before they are lowered into the trench to be laid.
- D. Materials, if stored, shall be kept safe from damage and shall not be stacked higher than the limits recommended by the manufacturer. The bottom tiers shall be kept off the ground on timbers, rails, or concrete. Pipe shall not be stored close to heat sources. The contractor shall be responsible for all security, damage and loss of pipe, excluding Acts of God.
- E. The interior of the pipe as well as all sealing surfaces of mating components (i.e. flange faces) shall be kept free from dirt or foreign matter at all times. The open ends of all sections of joined and/or installed pipe (not in service) shall be plugged to prevent insects, animals, or foreign material from entering the pipe line or pipe section. The practice of stuffing cloth or paper in the open ends of the pipe will not be permitted. Use waterproof nightcaps to prevent the entrance of any type of natural precipitation into the carrier or containment pipe and secure to the pipe in such a manner that the wind cannot blow them loose. Where possible, the pipe shall be raised and supported at a suitable distance from the open end such that the open end will be below the level of the pipe at the point of support.

3.03 RECEIPT INSPECTION

- A. All pipe and fittings shall be subjected to visual inspection at time of delivery and before they are installed or lowered into the trench to be laid. Defective, damaged, or unsound pipe will be rejected. Cuts, punctures, or gouges that penetrate or reduce the wall thickness by 10% or more are not acceptable and must be removed and discarded. Joints or fittings that do not conform to these specifications will be rejected and must be removed immediately by the Contractor.

3.04 FUSION AND JOINING**A. FUSION JOINING REQUIREMENTS:**

1. All PE-RT pipe shall be joined to by the heat fusion process which produces homogeneous, sealed, leak-tight joints. Tie-ins between sections of PE-RT pipe shall be made by butt fusion whenever possible.
2. **Butt Fusion:** The pipe shall be joined by the butt fusion procedure outlined in ASTM F2620 or

Questions? Get Technical Advice 800-345-ISCO (4726)

PPI TR-33. All fusion joints shall be made in compliance with the pipe or fitting manufacturer's recommendations. Fusion joints shall be made by qualified fusion technicians per ASTM F3190. A record or certificate of training for the fusion operator must be provided that documents training to the fundamentals of ASTM F2620. Considerations should be given to and provisions made for adverse weather conditions, such as temperatures below freezing, precipitation, or wind, which is accepted by the owner/engineer. The use of a controlled cooling cycle procedure to reduce cooling time is acceptable only as part of a controlled cooling cycle procedure where testing demonstrates that acceptable joints are produced using the controlled cooling cycle procedure.

B. FUSION OPERATORS:

1. The employer of the fusion machine operator is responsible for the fusion joint quality of the fusion weld made by that individual. The employer is responsible for documenting all training and qualification records for that individual, including compliance to any code requirements for fusion/bonder operators.
2. All HDPE fusion equipment operators shall be qualified to the procedure used to perform pipe joining. Fusion equipment operators shall have current, formal training on all fusion equipment employed on the project. Training received more than two years prior to operation with no evidence of activity within the past 6 months shall not be considered current.
3. For Projects with at least 5,000 feet or with pipe larger than 24 inches, operators or their supervisor must have a current McElroy Fusion Training Certificate for the equipment to be used on the project.
4. When the fusion machine operator is employed by the HDPE pipe and fusion machine supplier, the supplier shall maintain an ISO 9001 Certified Quality Management System.

C. BUTT FUSION EQUIPMENT:

1. For 6" and larger pipe sizes, the pipe butt fusion machine shall be a self-contained hydraulic fusion machine capable of butt fusing HDPE pipe. The carriage must be removable from the chassis for in-ditch use. The machine must be compatible with an electronic data recording device. Accessories will include all butt fusion inserts for the specified range of pipe sizes, a pyrometer kit for checking the surface temperature of the heater, extension cord of appropriate gauge (25' minimum), and hydraulic extension hoses (minimum of four). The butt fusion machine will be McElroy, or approved equivalent.
2. For 16" and larger pipe sizes, the butt fusion machine shall be capable of autonomously calculating the drag pressure and perform the shift sequence autonomously.
3. In areas where there may be insufficient space for layout of the entire length of fused pipe to be pulled-back, the Contractor shall utilize a continuous PE-RT pipe fusion equipment such as a PolyHorse by McElroy or other means to fuse the length of pipe necessary for the installation.

Questions? Get Technical Advice 800-345-ISCO (4726)**D. FUSION DATA RECORDING:**

1. McElroy DataLogger or equivalent fusion data recorder shall be used to record all fusion welds on hydraulically operated fusion machines. The device shall be capable of meeting the requirements of ASTM F3124, "Standard Practice for Data Recording the Procedure used to Produce Heat Butt Fusion Joints in Plastic Piping Systems or Fittings". The device, or combination of devices, shall record the following variables of each fused joint:
 - i. Heater surface temperature- immediately before inserting the heater plate, measure with a pyrometer and manually enter into the weld record.
 - ii. Gauge pressure during the initial heat cycle
 - iii. Gauge pressure and elapsed time during the heat-soak cycle
 - iv. Heater removal (dwell) time
 - v. Gauge pressure and elapsed time during the fusing/cool cycle
 - vi. Drag pressure
 - vii. Pipe diameter and wall thickness
 - viii. Type of HDPE material (Specification and Classification) and manufacturer
 - ix. Fusion Machine Identification
2. The device shall record the operator name and a unique operator ID number, along with the date and time of each weld.
3. Records showing the device is up to date on all required calibration should be available for presentation when requested.
4. All fusion welds should be traceable to the report (via operator and weld ID) with an indentation weld stamp or by permanent paint marker/pen next to fusion weld.
5. A weld location map may be requested, prior to commencement of work, by the owner or owner's representative.

E. BUTT FUSION EXAMINATION AND TESTING:

1. Examinations
 - i. **Visual:** For pipe sections, examine the full exterior circumference for bead uniformity before cutting. After cutting the pipe section, review the interior bead. All beads should have visually acceptable bead formation as shown in Fig 4 and Appendix X2 of ASTM F2620. In addition, the following characteristics are expected:
 1. There shall be no evidence of cracks or incomplete fusing
 2. There shall be no evidence of captured objects (e.g., pipe shavings, facer ribbons) between bonded surfaces.

Questions? Get Technical Advice 800-345-ISCO (4726)

3. Variations in upset bead heights on opposite sides of the cleavage and around the circumference of fused pipe joints are acceptable.
4. The apex of the cleavage between the upset beads of the fused joint shall remain above the base material surface
5. Fused joints shall not display visible angular misalignment, and outside diameter mismatch shall be less than 10% of the nominal wall thickness
6. Fusion data record review that meet criteria of section 3.04.D.1 can be used as additional verification of visual indicators.

ii. Fusion Data Record Review

The fusion data record for each fused joint shall be compared to the approved fusion procedure. The reviewer shall verify the following:

1. That all data required by section 3.04.D.1 was recorded
 2. Interfacial pressure was within the acceptable range
 3. Heater surface temperature was within the acceptable range
 4. Butt fusion pressure applied during the fusing/cool cycle was correctly calculated to include drag pressure, fell within the acceptable range for the applicable size and agrees with the recorded hydraulic fusing pressure.
 5. Butt fusing pressure was reduced to a value less than or equal to drag pressure at the beginning of the heat soak cycle.
 6. Fusing machine was opened at the end of the heat soak cycle, the heater was removed, and the end were brought together at the fusion pressure with the acceptable time range
 7. Cooling time at butt fusing pressure met the minimum time specified
- iii. If the recorded data in section 3.04.D.1 is outside the limits of the acceptable range, the joint is unacceptable, and must be removed and replaced.
 - iv. Frequency. Records for test fusion joints should be reviewed immediately after the joint is completed. Fusion joints for jobsite fusions should be reviewed daily or before being covered with backfill.

2. Mechanical Tests

- i. Contractor shall mechanically test the first fusion of each operator and each machine used on the project. Installation shall not continue until a fusion test has passed the test. Additional mechanical test are not required as long as long as the fusion are reviewed with the frequency specified in section 3.04.E.1.iv. Testing of fusion joints with no fusion data record review shall be at a frequency specified by the Owner or Engineer.
- ii. The fusion shall be allowed to cool completely, then fusion test straps shall be cut out.
- iii. All samples shall be labeled with operator information. Testing must be done at 73 degrees F plus or minus 5 degrees. The test temperature and sample size are critical to testing. Testing performed at cold or elevated temperatures may not give similar results to tests performed at ambient temperatures.

Questions? Get Technical Advice 800-345-ISCO (4726)

- iv. Each pipe sample weld shall be subjected to testing at two locations 180 degrees apart from each other in the joint weld. All specimens shall be tested by one of the following methods:
 1. Reverse Bend Test are allowed for pipe sizes 4" IPS or smaller. The specimens shall be prepared and tested in accordance with ASTM F2620, Appendix X4.
 2. Guided Side Bend Test are allowed for all wall thicknesses of 1" or greater. The specimens shall be removed and tested in accordance with ASTM F3183.
3. Hydrostatic Burst Test is allowed for pipe sizes 2"-24". The specimen length should measure 6 times pipe diameter with the butt fusion joint in the center of the specimen. The specimen should be tested in a tank filled with water, and testing conditions monitored and recorded with computerized equipment. The specimen will be tested at 4 times pipe rated pressure for 5 minutes with no failure of joint allowed.
- v. Results of any mechanical test should be documented. Information on the weld and operator should be transferred from the sample to the testing record.

3.05 INSTALLATION**A. DIRECT BURIAL**

1. Buried PE-RT pipe and fittings shall be installed per engineering drawings and ASTM D2774, ASTM D2321 and AWWA Manual of Water Supply Practices M55 Chapter 8. The Design Window identified in AWWA M55 Chapter 5 (page 65 of 2006 version) shall be considered acceptable design and installation conditions.
2. When moveable trench bracing such as trench boxes, moveable sheeting, shoring or plates are used to support the sides of the trench, care shall be taken in placing and moving the boxes or supporting bracing to prevent movement of the pipe, or disturbance of the pipe bedding and the backfill. Trench boxes, moveable sheeting, shoring or plates shall not be allowed to extend below top of the pipe. As trench boxes, moveable sheeting, shoring or plates are moved, pipe bedding shall be placed to fill any voids created and the backfill shall be re-compacted to provide uniform side support for the pipe.
3. Pipe embedment - Embedment material should be Class I, Class II, or Class III materials as defined by ASTM D-2321 Section 6. The use of Class IV or Class V materials is not recommended; however, they may be used only with the evaluation and approval of the engineer at a demonstrated achievable compaction
4. Bedding: Pipe bedding shall be in conformance with ASTM D2321 Section 8. Compaction rates should be as specified in ASTM D2321. Deviations shall be approved by the engineer.
5. Haunching and backfill shall be as specified in ASTM D2321 Section 9 with Class I, II, or III materials. Compaction shall be in excess of 85% Proctor, providing a minimum modulus of 1000 psi or greater.

Questions? Get Technical Advice 800-345-ISCO (4726)**B. PULL-IN INSTALLATION**

1. Per ASTM F1804 and/or www.HDPEapp.com, the contractor shall determine and document the maximum proposed pull-in length and pull-in force for the pressure class and pipe diameter to be pulled into an open trench. Pull-in lengths will not exceed the maximum lengths for the class and diameter pipe. A commercially available load limiter (weak link) approved by the Engineer shall be used between the puller and the pipe.
2. Prior to pulling the pipeline, contractor shall place rollers or other approved devices beneath the pipe to avoid unnecessary damage and to reduce pipe drag.
3. Trenchless installations:
 - i. For Horizontal Directional Drilling (HDD), refer to ASTM F1962, PPI TR-46, PPI PE Handbook (Chapter 12) and www.PPIBoreAid.com
 - ii. For sliplining, refer to ASTM F585, PPI PE Handbook (Chapter 11) and www.HDPEapp.com
 - iii. For pipe bursting, refer to PPI PE Handbook (Chapter 16)

C. APPURTENANCES

1. All appurtenances (tees, elbows, services, valves, air relief valves, fire hydrants, etc.), must be independently supported and shall not rely on the pipeline and its connections for this support. Excessive stresses may be encountered when appurtenances are inadequately supported.
2. Installation of Tracer Wire. When tracer wire is required, the Contractor shall install along the entire section of pipeline and along all service connections as listed below. The tracer wire shall be installed simultaneously with the polyethylene piping system. Tracer wire shall be installed by the Contractor once backfill has been placed and compacted to at least 12 inches above the top of the pipe and not more than 18 inches above the top of the pipe. Tracer wire shall be properly spliced at each end connection and each service connection. Care should be taken to adequately wrap and protect wire at all splice locations. No bare tracer wire shall be accepted. Provide Magnesium alloy anode for cathodic protection that conforms to the requirements of ASTM B843. Install tracer wire per local and manufacturer's requirements.

3.06 PIGGING, FLUSHING, CLEANING, AND DISINFECTING

- A. All mains shall be pigged, cleaned and flushed to remove all dirt, sand, debris and other foreign matter. The Contractor shall be responsible for developing a pigging and flushing plan to be submitted to the Engineer for approval prior to pigging and flushing.
- B. Disinfection:
 1. Cleaning and disinfecting of potable water systems shall be in accordance with AWWA C651 and AWWA M55 Chapter 10, and PPI Handbook of Polyethylene Pipe Chapter 2 (2nd Edition).
 2. The liquid disinfection chemical solution should be limited to less than 12% active chlorine. The time-duration of the disinfection should not exceed 24 hours. Chlorine tablets or powders are not permitted.

Questions? Get Technical Advice 800-345-ISCO (4726)

3. Upon completion, the system should be thoroughly flushed with fresh water, and retested to verify the disinfectant chlorine level has been reduced to potable drinking water concentrations in all service water tubing and branch lateral pipes

3.07 TESTING AND LEAKAGE

- A. The contractor shall ensure testing can be accomplished in a safe manner, including protection of personnel, equipment, and public in the event of a failure during testing. The contractor shall restrain pipe, components, and test equipment as required. All pumps, valves, temporary connections, meters, gauges and other measuring devices shall be furnished, installed and operated by the Contractor and all such equipment and devices and their installation shall be approved by the Owner's Engineer.
- B. The pressure gauges or data recorders should be calibrated and sufficiently sized to provide mid-range data that result in easy reading, interpretation. Gauges shall be accurate to within 2% of full scale
- C. The test pressure may be up to 1.5 times the system design pressure, based on the lowest point in elevation in the test section. The contractor shall ensure that the designated test pressure does not exceed the maximum allowable test pressure specified by the manufacturer for any component in the test section.
- D. Test pressures require consideration of thermal conditions. Polyethylene piping materials are typically pressure rated at 73°F (23°C) and PE piping at temperatures greater than 80°F (26°C) require reduced test pressures. (Note that higher pipe temperatures should consider both ambient temperatures and radiant solar heating of exposed black HDPE pipe) Guidance for elevated temperatures can be found in the appendix of Chapter 3 (Material Properties) of the PPI Handbook of PE Pipe.
- E. Gravity Pipelines - The Contractor shall perform a low-pressure air test for gravity flow pipelines to the requirements and specifications of ASTM F1417. Warning: All pneumatic test, regardless of pressure, can be dangerous and safety procedures shall be identified, documented, approved by the owner and engineer, and followed.
- F. Pressure Pipelines - Pressure testing shall be conducted in accordance with requirements and recommendations of ASTM F2164 (Field Leak Testing of Polyethylene Pressure Piping Systems Using Hydrostatic Pressure), AWWA M55 Chapter 9, and PPI Handbook of Polyethylene Pipe Chapter 2 (2nd Edition). Pneumatic (compressed air) leakage testing of HDPE pressure piping is prohibited for safety reasons.
 1. The section of pipe to be tested shall be filled with potable or generally clean water (uncontaminated river/lake water) approved by the Owner/Engineer. While the system is being filled with water, air shall be carefully and completely exhausted.
 2. The test procedure for PE-RT pipe consists of two steps: 1) the initial phase or expansion phase and 2) the test phase. During the initial/expansion phase, sufficient make-up water shall be added hourly for 3 hours to return to the test pressure. During the test phase, the expansion phase pressure is reduced by 10 psi to test phase pressure and monitored for at least one hour (3 hours maximum).
 3. Under no circumstances shall the total time under test exceed eight (8) hours. If the test is not completed due to leakage, equipment failure or any other reason, depressurize the test section and permit the system to "relax" for eight (8) hours prior to the next testing sequence.

Questions? Get Technical Advice 800-345-ISCO (4726)

4. In accordance with section 9.8 of ASTM F2164, the pipe shall pass if the final pressure is within 5% of the test phase pressure for the testing period (3 hours maximum). If the test section fails this test, the Contractor shall repair or replace all defective materials and/or workmanship at no additional cost to the Owner.
- G. All pressure and leakage testing shall be done in the presence of a representative of the Owner and Engineer.

END OF SECTION